



विराटनगर महानगरपालिका
नगर कार्यपालिकाको कार्यालय
विराटनगर, मोरङ, कोशी प्रदेश, नेपाल
निर्माण कार्यको दररेट पेश गर्ने सम्बन्धी सूचना
सूचना प्रकाशित मिति: २०८३।०२।२८

यस महानगरपालिकाबाट सञ्चालन हुने प्रदेश सरकार सशर्त अनुदान पूँजीगततर्फ विनियोजित तपसिल अनुसारको कार्य सोझै खरिद(Direct Quotation) प्रक्रिया मार्फत गर्नुपर्ने भएकाले सूचीकृत, इच्छुक र इजाजत प्राप्त फर्म/कम्पनी/संस्थाले देहाय बमोजिमको शर्तहरूको अधिनमा रही स्पेशिफिकेशन सहित दररेट पेश गर्नुहुन यो सूचना प्रकाशन गरिएको छ ।

तपसिल

क्र. सं.	योजनाको नाम	दररेट पेश गर्ने अन्तिम मिति	कैफियत
१	३ नं.वडा कार्यालयको दक्षिणपट्टी खाली रहेको जग्गामा पार्क निर्माण	सूचना प्रकाशित मितिले ३(तीन) दिन	

१. दररेट पेश गर्ने दाताहरूले थप जानकारी र BOQ यस महानगरपालिकाको Website: biratnagarmun.gov.np तथा योजना तथा पूर्वाधार विकास महाशाखाबाट प्राप्त गर्न सकिनेछ ।
२. दररेटमा आइटम अनुसार अंक र अक्षर महल दुवैमा रकम अनिवार्य लेख्नु पर्नेछ ।
३. दररेट पेश गर्दा ठे. इजाजत प्रमाणपत्र, मु.अ.कर प्रमाणपत्र, आ.व.२०८१।०८२ सम्मको कर चुक्ता प्रमाणपत्र प्रतिलिपि, स्थानीय तहमा दर्ता भएको व्यवसाय प्रमाणपत्रको प्रतिलिपिका साथ सिलबन्दी गरी पेश गर्नुपर्नेछ ।
४. अन्य कार्यविधि सार्वजनिक खरिद ऐन, २०६३ र सार्वजनिक खरिद नियमावली, २०६४(संशोधन सहित) एवम् प्रचलित कानून बमोजिम हुनेछन् ।

(स) ०२/०२/२८
०२३/०२/२८
प्रमुख प्रशासकीय अधिकृत

Biratnagar Metropolitan City
Office of the Municipal Executive
Biratnagar, Koshi

F.Y : 2082/23

Name of The project: Ward Parking
 Location of the Project: Biratnagar - 3

Fiscal Year :- 2082 / 083

Bill of Quantity (BOQ)

S.N.	Description of works	Quantity	Unit	Rate		Amount	Remarks
				In Figures	In Words		
1	Providing and Installing Information Board Made of Flex Print of size 1.8m x 1.2m and Hard Paper Color Photograph of Various Site activities as per instruction of engineer With VAT	1.00	Job				
2.0	Earthwork in excavation in ordinary soils in foundation including all hauling distance and all lift complete.(dewatering include)	24.18	Cum				
3.0	Broken Brick Soling on the prepared surface with manual compaction to design line and level as per drawing and instruction of engineer	29.59	Sqm				
4.0	Plain cement Concrete (PCC) in 1:2:4 ratio with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	1.83	Cum				

CH

Biratnagar Metropolitan City
Office of the Municipal Executive
Biratnagar, Koshi



Name of The project: Ward Parking
 Location of the Project: Biratnagar - 3


Fiscal Year :- 2082 / 083

Bill of Quantity (BOQ)

S.N.	Description of works	Quantity	Unit	Rate		Amount	Remarks
				In Figures	In Words		
5.0	First Class Brickwork in 1: 6 C/S mortar in perfect line level finish including wetting the bricks, racking the joints and curing the work for at least 7 days including 30 m lead and lift all complete	18.60	Cum				
6.0	Tor steel or TMT reinforcement bar of FE 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design including lead and lift all complete.	870.81	K.g				
7.0	Plain cement Concrete (PCC) for RCC works (1:1.5:3) with approved quality of cement and sand and crushed stone aggregate including mixing, laying using mixture & Vibrator, curing etc all complete in approval of site engineer	10.50	Cum				
8.0	Supply and Installation of Formwork in Columns with approved materials, necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding net.	90.66	Sqm				

CH

Biratnagar Metropolitan City
Office of the Municipal Executive
Biratnagar, Koshi



FY : 2082/83

Name of The project: Ward Parking
 Location of the Project: Biratnagar - 3

Fiscal Year :- 2082 / 083

Bill of Quantity (BOQ)

S.N.	Description of works	Quantity	Unit	Rate		Amount	Remarks
				In Figures	In Words		
9.0	Providing and applying 12.5 mm thick Plaster with Cement Mortar 1:4 (1 cement : 4 sand) on brick work structure as per Technical	171.70	Sqm				
10.0	Supplying and fixing of Iron gate made up of 16 gauge black sheet on 50 X 50 X 5 mm M.S. angle frame including with all necessary accessories, all complete	9.12	Sqm				
Total of Civil Works							
Vat @ 13% of Civil Works							
Grand Total							

Total Estimated Cost Excluding VAT & P.S.: Nrs 857,569.75

Total amount in words

Name of Contractor :

Address :

Signature of Contractor :

E-mail :